

PHASE 1 GEOTECHNICAL REPORT

PROPOSED SUBSIDY HOUSING PROJECT, PORTION 111 OF MELKHOUTONTEIN, STILBAAI, WESTERN CAPE PROVINCE

20 February 2018 (Rev 0)



Prepared by:
OUTENIQUA GEOTECHNICAL SERVICES
18 CLYDE ST
KNYSNA
6571
www.oudeniqua.co.za




Prepared for:
ASLA DEVCO
25 CONRADIE CRESCENT, STRAND
PO BOX 118, GORDONS BAY, 7151
TEL: +27 (0)21 8458335
www.asla.co.za



Ref: 2017\Asla Devco\Melkhoutfontein\Phase 1 Geotech Report 20.02.2018 Rev0

Report review history:

Revision No	Date	Prepared by:	Reviewed by:
0	20.02.2018	I.Paton Pr.Sci.Nat	S Ngema
			

Authors qualifications and affiliations:

Iain Paton has a Bachelor's degree in Geology and a Master's degree in Geotechnical Engineering and is a registered professional with the South African Council for Natural and Scientific Professions (Pr Sci Nat # 400236/07) with 19 years' experience in the construction, mining and energy and industries. Iain Paton is a member of the South African Institute of Engineering and Environmental Geologists (SAIEG), the Geotechnical Division of the South African Institute of Civil Engineering (SAICE), the South African Institute of Rock Engineering (SANIRE) and the Institute of Municipal Engineering of South Africa (IMESA).

Declaration of independence:

The author of this report is independent professional consultant with no vested interest in the project, other than remuneration for work associated with the compilation of this report.

General limitations:

1. The investigation has been conducted in accordance with generally accepted engineering practice, and the opinions and conclusions expressed in the report are made in good faith based on the information at hand at the time of the investigation.
2. The contents of this report are valid as of the date of preparation. However, changes in the condition of the site can occur over time as a result of either natural processes or human activity. In addition, advancements in the practice of geotechnical engineering and changes in applicable practice codes may affect the validity of this report. Consequently, this report should not be relied upon after an elapsed period of one year without a review by this firm for verification of validity. This warranty is in lieu of all other warranties, either expressed or implied.
3. Unless otherwise stated, the investigation did not include any specialist studies, including but not limited to the evaluation or assessment of any potential environmental hazards or groundwater contamination that may be present.
4. The investigation is conducted within the constraints of the budget and time and therefore limited information was available. Although the confidence in the information is reasonably high, some variation in the geotechnical conditions should be expected during and after construction. The nature and extent of variations across the site may not become evident until construction. If variations then become apparent this could affect the proposed project, and it may be necessary to re-evaluate recommendations in this report. Therefore, it is recommended that Outeniqua Geotechnical Services is retained to provide specialist geotechnical engineering services during construction in order to observe compliance with the design concepts, specifications and recommendations and to allow design changes in the event that subsurface conditions differ from those anticipated prior to the start of construction. Any significant deviation from the expected geotechnical conditions should be brought to the author's attention for further investigation.
5. The assessment and interpretation of the geotechnical information and the design of structures and services and the management of risk is the responsibility of the appointed engineer.

EXECUTIVE SUMMARY

Outeniqua Geotechnical Services was appointed by Asla Devco to undertake a Phase 1 geotechnical site investigation for a proposed subsidy housing project on a greenfield site on Portion 111 of Melkhoutfontein 480 Stilbaai in the Western Cape Province. The project includes the construction of roads, services and numerous single and/or double storey masonry housing units.

The site investigation included a detailed desktop study and a subsurface investigation, involving a series of test pits, *in situ* tests and laboratory tests, culminating in a factual and interpretative report with recommendations for the engineering design.

The climate of the region can be classified as temperate, with cool winters and warm summers, and most rainfall occurring during the winter months. The Weinert Climatic-N No. for the area is 3-4, indicating a moderate climate.

The topography is characterized by gently sloping terrain with several small, wide ephemeral drainage lines traversing the site, which drain the site in a southeast direction into the tributaries of Goukou river. The natural vegetation consists of dense coastal fynbos vegetation. The surface conditions on the site were generally dry at the time of the investigation and access across the site with machinery was relatively easy in areas that had been cleared of vegetation.

The geology of the site consists of Tertiary-age Wankoe Formation of the Bredasdorp Group. This formation is composed of unconsolidated to semi-consolidated aeolian sands and calcarenite rock. The geology is generally suitable for urban development and has a low seismic activity.

The soil profile is quite variable across the site, which is typical in this geological formation, as the pedogenic cementation process of the insitu marine and aeolian sediments varies widely. The soil types are dominated by silty fine aeolian sands and sandy silt (rock flour) or gravelly sands derived from the weathering of the calcarenite/calcrete rock, which is exposed in low outcrops on parts of the site. Several of the test pits refused at shallow depths on this soft rock. The plasticity index and clay content of the soils is low, and the soils will display negligible heave. Some of the weakly cemented soils may display a collapse potential when saturated under load. Groundwater was only encountered in one test pit on the southeast corner of the site (the lowest part of the site), adjacent to a natural drainage line.

Significant bush clearing will be required to clear the site although this should be relatively easy. Bulk earthworks, platforming and low retaining walls may be required on moderately sloping parts of the site where slopes exceed 1:10. Excavations to 0.5m are classified as "soft", and all excavations below this level are classified as "intermediate" or "hard".

The recommended foundation types for the proposed structures are lightly reinforced strip foundations or light rafts on compacted insitu soils on flat sites; or engineered platforms on sloping sites (cut to fill, using suitable granular insitu soils). Bearing pressures should be limited to 75kPa to minimize settlement.

The site geology and geotechnical conditions are generally considered suitable for the proposed development, but there are some geotechnical constraints that may affect subsidy variations and will require attention from the structural and civil engineers.

Table of Contents

1. Introduction and terms of reference.....	1
2. Information available.....	2
3. Nature of the investigation	2
4. Site description.....	2
5. Geology.....	4
6. Geotechnical Evaluation	4
6.1 Engineering and material characteristics.....	4
6.1.1 Topography, slopes and vegetation cover	4
6.1.2 Soil types and rock.....	6
6.1.3 Grading, Atterberg limits and potential expansiveness.....	8
6.1.4 Moisture/density relationship and CBR	9
6.1.5 pH and conductivity.....	10
6.1.6 Compressibility, collapse potential and bearing capacity	10
6.1.7 Swell / heave	11
6.1.8 Soil moisture, permeability and groundwater	11
6.1.9 Existing structures	11
6.2 Slope stability and erosion	12
6.3 Excavation classification with respect to services	12
6.4 Impact of the geotechnical character of the site on subsidy housing developments.....	12
7. Site classification	14
8. Foundation recommendations and solutions	14
8.1 Earthworks and structural foundations	15
8.2 Road pavements	16
9. Storm water drainage recommendations	16

10. Special precautionary measures	17
11. Conclusions	17

List of appendices

Appendix 1 – Maps

Appendix 2 - Soil profiles

Appendix 3 - Lab tests

Appendix 4 - DCP tests

1. Introduction and terms of reference

Outeniqua Geotechnical Services was appointed by Asla Devco to conduct a Phase 1 geotechnical site investigation for a proposed subsidy housing project on Portion 111 of Melkhoutfontein in Stilbaai, in the Western Cape (see locality map in **Figure 1**).

The project consists of new government subsidy housing units, new access roads and services. The physical and geotechnical nature of the site needs to be investigated in order to facilitate the civil engineering design and project planning process.




Figure 1: Locality map

The investigation is carried out in accordance with SANS 634: Geotechnical Investigations for Township Developments.

The general purpose of the investigation is to:

- Describe the location, topography and geology of the proposed site;
- Investigate and describe the soil types and expected founding conditions;
- Highlight any problem soils, slope stability or drainage issues;
- Estimate the bearing capacity, settlement and/or swell potential of the soil;
- Classify the excavations in terms of SABS 1200D;
- Determine the suitability of the site for housing purposes and make recommendations for the design of earthworks, foundations and engineering services.

2. Information available

The following maps and plans were available for reference purposes and may be reproduced in this report:

- Topocadastral data, obtained from the National Geospatial Information Department;
- 1:250 000 and 1:50 000 Geological maps of the area, obtained from the Council for Geoscience;
- 1:1000000 Seismic Hazard Map of SA, obtained from the Council for Geoscience.
- Site layout plans provided by Asla Devco

3. Nature of the investigation

The Phase 1 site investigation involved a desktop study and a detailed subsurface investigation on the site. The subsurface investigation involved conducting a total of 19 test pits across the site with a TLB/Backactor to a depth of 2.5m or shallower refusal, to obtain an indication of the expected geotechnical conditions of the area. Test pits were profiled by a qualified geologist and samples of various soil horizons were collected for laboratory tests. Insitu penetration tests by means of a DCP were conducted from ground level next to each test pit.

Soil samples were taken for the following lab tests to determine the engineering characteristics of the soil:

- Foundation Indicator tests (TMH1 and ASTM) to determine gradings, Atterberg limits and potential expansiveness (tested at Outeniqua Lab in George);
- MOD/CBR/Indicator tests (TMH1) to determine the compaction/strength properties (tested at Outeniqua Lab in George);
- pH and Conductivity tests (TMH1) to determine soil aggressiveness (tested at Controlab in East London).
- Swell/Collapse potential tests (ASTM) to determine soil swell, collapse and compressibility characteristics (tested at Controlab in East London).

The confidence in the information gained from the investigation is high, and further investigations are not deemed necessary at this stage of the project.

4. Site description

The site is a vacant/greenfield portion of Farm 480, which is located in the Melkhoutfontein area approximately 5km north of the coastal village of Stilbaai. The terrain on the site slopes gently to moderately (1:20 to 1:10) to the south east with localized topographic depressions. The site drains towards the southeast into the tributaries of Goukou river and there are a few ephemeral drainage lines crossing the site (see **Figures 2 & 3**). The vegetation is dominated by thick coastal fynbos bush and small trees (see **Figure 4**). The climate of the area is temperate with a Weinert climatic N-value of 3-4 (moderate). The surface conditions on the site were generally dry at the time of the investigation, and access was easily gained in areas that had been previously cleared of dense bush.




Figure 2: Topographic map of site




Figure 3: Aerial photo of site



Figure 4: Showing typical topography and vegetation

5. Geology

The geology of the area consists of calcarenite and aeolian sands with calcareous-cemented lenses of the Tertiary-aged Wankoe Formation of the Bredasdorp Group (light green on the map in **Figure 5**). The formation consists of yellowish grey to yellowish orange, well-rounded, well sorted, fine- to coarse-grained quartz grains, glauconite and finely comminuted shell fragments (see **Figure 6**). The formation also consists of unconsolidated to semi-consolidated sands with inconspicuous cross bedding. The Bredasdorp Group is known to contain some localised karstic features which can develop in calcareous formations, mainly consisting of dolines (depressions caused by chemical solution of calcareous rocks), but there are no dolomitic rocks and the risk of any significant sinkholes or unstable geology on this particular site is low. There are no significant geological faults near the site, and the geology is generally suitable for urban development, with a low seismic activity risk.

6. Geotechnical Evaluation

6.1 Engineering and material characteristics

6.1.1 Topography, slopes and vegetation cover

Results of the investigation

The site is characterized by gentle to moderately sloping terrain which drains to the south east into tributaries of the Goukou river. The slope gradients vary from 1:30 to 1:10 but there are some localized flat areas and even topographic depressions. The vegetation on the site is dominated by thick bush and small trees.

Effect on the proposed development

The general topography is suitable for subsidy housing projects. Vegetation clearing will be relatively easy with a bulldozer.




Figure 5: Geological map



Figure 6: Hand specimen of the Calcarene of the Wankoe Formation

6.1.2 Soil types and rock

Results of the investigation

The soil profile is quite variable across the site, but generally consists of a transported topsoil horizon, consisting of silty sand and organic humus, which is underlain by soft to medium hard rock calcarenite or calcrete hardpan, which is underlain by unconsolidated to semi consolidated sand with marine shell fragments (see **Figure 7**). The calcarenite/calcrete hardpan layer is highly to completely weathered in places, resembling residual gravel, angular cobbles and/or small boulders (see **Figure 8**). The calcarenite/calcrete also occurs in low outcrops in several places across the site (see **Figure 9**) and several of the test pits refused at shallow depths on this hard, cemented layer. No significant uncontrolled fill material, such as rubbish or rubble was noted on the site.

Effect on the proposed development

The soils are generally not severely problematic but significant variations in soil structure and density warrants a conservative approach to foundation design. Several shallow refusals indicate potentially hard excavation conditions across many parts of the site. Recommendations are given in **Chapter 8**.



Figure 7: Typical soil profile encountered in test pits



Figure 8: Calcarenite cobbles and boulders encountered at TP10



Figure 9: Calcarenite outcrop encountered near TP1

A summary of the test pit data and the thickness of the different soil horizons is provided in **Table 1**.

Table 1: Summary of soil horizons recorded in test pits (in mm)

<i>Test pos. No.</i>	<i>Imported (fill) soil</i>	<i>Transported soil</i>	<i>Residual soil</i>	<i>Rock</i>	<i>Total depth of test pit</i>	<i>Refusal?</i>
TP1	-	-	-	430	430	Yes
TP2	-	150	-	50	200	Yes
TP3	-	2300	-	-	2300	No
TP4	-	2600	-	-	2600	No
TP5	-	3000	-	-	3000	Yes
TP6	-	2500	-	-	2500	No
TP7	-	400	-	-	400	Yes
TP8	-	1500		400	1900	No
TP9	-	-	150	-	150	Yes
TP10	-	-	300	-	300	Yes
TP11	-	200	-	-	200	Yes
TP12	-	1600	-	-	1600	Yes
TP13	-	400	-	-	400	Yes
TP14	-	2200	-	-	2200	No
TP15	-	2300	-	-	2300	No
TP16	-	100	-	150	250	Yes
TP17	-	300	400	200	900	Yes
TP18	-	200	-	-	200	Yes
TP19	150	-	-	150	300	Yes

6.1.3 Grading, Atterberg limits and potential expansiveness

Results of the investigation

Representative samples of different soil horizons were collected for Foundation Indicator tests in order to determine their basic geotechnical properties, estimate potential expansivity and evaluate their suitability as founding mediums. Abbreviated results of the tests are shown in **Table 2**. The samples tested are classified into the following categories under the Universal Soil Classification system:

ML - Inorganic silts, non-plastic silts, rock flour;
 SM-SC – Silty sands, clayey sands;
 SP-SM – Poorly graded sands, silty sands.

The tests confirm that all the samples tested are classified as fine granular soils (sands) or rock flour, with significant fines (clay and/or silt) in only a few samples. The plasticity index in all samples is typically less than 5 and the potential expansiveness is low/negligible.

Table 2: Grading and Atterberg limits test results summary

Test Pit No	Sample Depth (mm)	Atterberg Limits			Particle Analysis (%)				MC*	PE**	USC ***
		PI	LL	LS	Clay	Silt	Sand	Grave I			
TP3	1700-2300	3	20	1.5	19	5	74	2	13.2	Low	SM
TP4	200-800	4	23	2	9	9	54	28	16	Low	SM-SC
TP4	800-1400	NP	NP	0	11	5	83	1	12.6	Low	SM
TP4	1400-3000	2	18	2	19	6	75	0	23.2	Low	SM
TP6	1500-2500	2	16	1	13	4	83	0	18.9	Low	SM
TP7	0-400	NP	NP	0	2	4	94	0	6.9	Low	SP-SM
TP12	0-300	2	21	1	9	9	60	22	15.6	Low	SM
TP12	700-1600	NP	NP	0	24	25	48	3	6.5	Low	ML
TP14	300-2200	NP	NP	0	4	3	47	46	8.3	Low	SP-SM
TP17	300-700	3	16	1	24	13	48	15	14.4	Low	SM

* Moisture content ** Potential expansiveness (Skempton's activity chart) *** Unified Soil Classification System

Effect on the proposed development

The insitu soils are not considered too problematic in terms of moisture sensitivity or heave, but may display some compressibility or collapse potential, which may have an impact on earthworks and affect foundation design. Foundation recommendations are given in **Chapter 8**.

6.1.4 Moisture/density relationship and CBR

Results of the investigation

Representative samples of soils were collected for Mod/CBR/Indicator tests in order to determine the moisture-density relationship, compaction and CBR properties for road subgrade and general filling purposes. The results of the tests are summarised in **Table 3**.

Table 3: CBR test results summary

Test Pit No	Sample Depth (mm)	CBR at					Swell %	PI %	GM	MDD/ OMC	TRH14 Class
		100 %	98%	95%	93%	90%					
TP5	0-900	38	33	25	17	10	0.00	NP	1.01	1842/9.7	G7
TP12	300-700	68	56	43	28	14	0.00	3	1.78	1775/15.3	G6
TP14	300-2200	52	41	27	20	12	0.00	NP	2.13	1858/11.6	G7
TP15	250-800	65	30	31	20	21	0.00	NP	2.25	1812/15.4	G7

The results indicate that the soils are generally good subgrade quality (G6 to G7 under the TRH14 system, A1 to A2-6 under the AASHTO system) and are potentially useful in engineered fill platforms, filling under floor/raft slabs and selected subgrade layers for roads.

Effect on the proposed development

Savings can be made by using the insitu soils as a natural fill material and selected subgrade material and road layerworks. Recommendations for structures and roads are given in **Chapter 8**.

6.1.5 pH and conductivity

Results of the investigation

Samples of *in situ* soils were collected for soil chemistry tests (pH & Conductivity) in order to determine the aggressiveness of the soil which can affect buried services and concrete foundations. A summary of the results of the pH and conductivity tests are shown in **Table 4**.

Table 4: pH and conductivity test results summary

<i>Test Position</i>	<i>Depth</i>	<i>pH</i>	<i>Conductivity (mS/m)</i>
TP4	800-1500	7.57	1843
TP7	0-400	6.66	1441
TP17	300-700	8.20	N/A

Corrosion of metallic pipe fittings and concrete reinforcement may be negatively influenced by low or high pH, and high conductivity (indicating high concentration of dissolved salts in the soils). An indication of the influence of pH and conductivity on the corrosiveness of soil is given in **Table 5**.

Table 5: Influence of pH and conductivity on the corrosiveness of soil

<i>pH</i>	<i>Conductivity (mS/m)</i>	<i>Potential Corrosiveness</i>
7-8	<10	Non-corrosive
5-6 or 9-10	10-20	Mildly corrosive
3-4 or 11-12	20-50	Corrosive
<3 or >12	>50	Highly corrosive

The lab results indicate high salts concentration which will be highly corrosive and aggressive towards buried metallic fittings.

Effect on the proposed development

Standard HDPE or uPVC pipe products will be suitable and buried metallic valves and fittings should be epoxy powder coated as standard. A minimum 40mm rebar cover in buried concrete foundations is recommended as a standard.

6.1.6 Compressibility, collapse potential and bearing capacity

Results of the investigation

In situ penetration tests (DCP) indicate significant variation in the consistency of the soil in the upper 0.7m of the profile, but consistently dense conditions below this level. Observation in test pits indicate significant variation in soil texture, structure and density throughout the profile, which means that compressibility will be difficult to predict. Consolidation/collapse potential tests were not very successful due to the friable nature

of the slightly cohesive or weakly cemented soils, which tended to break up on sampling or preparation. Some soils with low densities and fine pinhole texture were observed in some of test pits, indicating a potentially compressible and/or collapsible fabric. However, bearing capacity for light structures is not considered a major problem due to the presence of significantly dense soil horizons, and even hardpan lenses, which significantly improve bearing capacity. Settlement may be a concern if loose sandy soils are not adequately compacted to increase density.

Effect on the proposed development

Improvement (compaction) of the founding conditions and improved/modified foundations will be required to prevent differential settlement. Foundation recommendations are discussed in more detail in **Chapter 8**.

6.1.7 Swell / heave

Results of the investigation

Foundation Indicator test results reported a low potential expansiveness. No heave is expected.

Effect on the proposed development

No extra precautions are required to cater for heave.

6.1.8 Soil moisture, permeability and groundwater

Results of the investigation

The site is located in a temperate, moderate climatic area which experiences seasonal wet conditions (Weinert-N Climatic No. 4). A detailed study of the contour plan reveals some significant undulations in the surface topography and some poorly defined ephemeral drainage lines crossing the site. Generally, the site drains towards the southeast but there are some localised depressions which could be poorly drained, particularly in the western and southeastern parts of the site. In general, the soil permeability is medium, but the presence of cemented calcarenite rock/ hardpan layers will negatively affect infiltration of storm water, resulting in significant run-off or ponding on surface.

Effect on the proposed development

Groundwater is highly unlikely to have a significant effect on foundations or earthworks. The design of stormwater systems must take into account the site topography for suitable stormwater discharge points. Recommendations for site drainage and stormwater design are given in **Chapter 9**.

6.1.9 Existing structures

Results of the investigation

There are no existing structures onsite.

Effect on the proposed development

Demolition of structures and relocation of inhabitants will not be necessary.

6.2 Slope stability and erosion

The natural slope gradient is gentle to moderate and there are no signs of macro slope instability on the.

Temporary shallow excavations are likely to be generally stable but deep excavations exceeding 1.5m high should be battered to safe working angle of 35° and assessed by the engineer.

6.3 Excavation classification with respect to services

Shallow refusal was recorded with a TLB/back-actor in many of the test pits and depths ranging from 0.1m to 0.5m. In most cases, excavations to a depth of 0.5m can be accomplished with a TLB and are classified as soft in terms of SABS 1200D, but a 30t excavator with a rock bucket attachment will be required to excavate below this depth in many areas, and therefore excavations below 0.5m are classified as “intermediate or hard” for preliminary costing purposes.

6.4 Impact of the geotechnical character of the site on subsidy housing developments

The geotechnical subsidy variations are tabulated in **Table 6**.

Table 6: Site specific geotechnical subsidy variations

<i>Geotechnical Conditions</i>	<i>Category or type</i>	<i>Criteria</i>	<i>Precautionary measures</i>	<i>Applicable areas</i>	<i>Comment</i>
Seepage / groundwater	Category 1	Permanent or perched water tables less than 1.0m below ground surface	Subsurface drainage/improved damp-proofing measures to houses, service trenches to be dewatered during construction	None	
	Category 2	Permanent or perched water tables more than 1m but less than 1.5m below ground level	Service trenches to be dewatered during construction	None	
Erodability of soil	Category 1	High risk (Erodability index 1-8)	Retaining walls & earthworks to reduce slopes & surface drainage	None	
	Category 2	Medium risk (Erodability index 9-15)	Retaining walls & earthworks to reduce slopes	Yes	
Hard excavation	Category 1	Hard rock excavation to a depth of 1.5m	Additional cost of trench and foundation excavation	All areas	
	Category 2	Boulder excavation to a depth of 1.5m	Additional cost of trench, foundation and road excavation	None	
Dolomite	Category 1	Risk class 1&2 (Dolomite area class D2)	Additional cost of foundations	None	
	Category 2	Risk class 3&4 (Dolomite area class D3)	Additional cost of foundations	None	

Geotechnical Conditions	Category or type	Criteria	Precautionary measures	Applicable areas	Comment
Expansive Clays	Category 1	H1	Foundation design, building procedures and precautionary measures: Modified normal	None	
	Category 2	H2	Foundation design, building procedures and precautionary measures: Light/medium raft	None	
	Category 3	H3	Foundation design, building procedures and precautionary measures: Heavy raft	None	
Compressible and Collapsible soils	Category 1	C1	Foundation design, building procedures and precautionary measures: Modified normal	All areas	
	Category 2	C2	Foundation design, building procedures and precautionary measures: Light or heavy raft	None	
Compressible soils	Category 1	S1	Foundation design, building procedures and precautionary measures: Modified normal	None	
	Category 2	S2	Foundation design, building procedures and precautionary measures: Light or heavy raft	None	
Mining subsidence	Category 1	Old undermining to a depth of between 90-240m below surface where slope closure has ceased	Additional cost of foundations: Compaction below footings or raft	None	
	Category 2	Old undermining to a depth of between 90-240m below surface where total extraction has taken place	Additional cost of foundations: additional earthworks or soil reinforcement	None	
Seismic activity	Category 1	Mining induced seismic activity > 100cm/s ²	Additional cost of foundations: Stiffened strip footings or raft	None	
	Category 2	Natural seismic activity > 100cm/s ²	Additional cost of foundations: Stiffened strip footings or raft	None	
Topography	Category 1	Average ground slope flatter than 1:20	Increase depth of sewer & provision of pump station		
	Category 2	Average ground slope of between 1:11 and 1:20	Terracing for houses & additional earthworks to roads & storm water control measures	All areas	Average slope Estimated

<i>Geotechnical Conditions</i>	<i>Category or type</i>	<i>Criteria</i>	<i>Precautionary measures</i>	<i>Applicable areas</i>	<i>Comment</i>
	Category 3	Average ground slope of between 1:7.5 and 1:10	Terracing for houses & additional earthworks to roads & storm water control measures		
	Category 4	Average ground slope of between 1:5 and 1:7.4	Terracing for houses & additional earthworks to roads & storm water control measures		
	Category 5	Average ground slope steeper than 1:5	Terracing for houses & additional earthworks to roads & storm water control measures		
SCCCA	Southern Cape Coastal Condensation Area	Area subjected to severe condensation conditions	Plaster and paint on all external walls & 6.4mm gypsum plasterboard ceilings & 80mm thick glass fibre insulation	All areas	
Location of development site		Site more than 20km from major centres	Additional cost of transportation	All areas	Mossel Bay 85km

7. Site classification

The site is broadly mapped according to distinguishable geotechnical terrains and the applicable residential site designations, according the SAICE Code of Practice for Single Storey Structures of Masonry Construction (1995), are assigned to each terrain as shown in **Table 7** (also refer to **Figure 10**). The entire the site is classified as one single terrain (Terrain 1) which is characterised by potentially compressible and/or collapsible soils with less than 10mm potential movement (C1), and shallow rock or hardpan at a depth less than 1.5m (R). The presence of hard rock or hardpan may not occur over the entire site, but it is unpredictable and not worth trying to distinguish between areas where shallow refusals occurred and where they didn't, and it is more practical to apply a blanket classification across the entire site.

Table 7: SAICE site classification

<i>Terrain Unit</i>	<i>Geotechnical Constraint</i>	<i>Expected movement (mm)</i>	<i>NHBRC Site Classification</i>
Terrain 1	Compressible and/or collapsible soil	< 10	C1
	Shallow rock	-	R

8. Foundation recommendations and solutions

The following recommendations are provided in good faith and are based on the information gained from the investigation. Although the confidence in the information is high, some variation can be expected between the data points and the design engineers should take cognisance of this. The design of structures and services remains the responsibility of the appointed engineers. Any significant variation from the expected geotechnical conditions should be brought to the author's attention for comment.




Figure 10: Geotechnical map

8.1 Earthworks and structural foundations

Earthworks should be conducted in accordance with SABS 1200D, COLTO 3300 and/or other applicable standard specifications. Foundations should be constructed in accordance with the NHBRC Home Builders Manual, SANS 10400-H and/or other applicable standards or as otherwise directed by the engineer.

Organic matter and any organic-rich topsoil and should be cleared from the site area before bulk earthworks commence. The insitu soils are suitable for use as natural fill materials for platforms, bulk fills on roads, and even possibly under floor slabs/rafts with minimal selection required to remove oversize particles (boulders) which may hamper compaction. Boulders exceeding 0.3m should be cut to spoil. At the engineer's discretion, allowance can be made for importation of G7 selected material for high quality filling purposes under floors. Soil obtained from excavations for service trenches and road box cuts should be approved by the civil engineer before placement (minimum G9 recommended quality). Bulk fill compaction should be carried out at optimum moisture content and the minimum recommended density is 93% of the Mod AASHTO maximum dry density. In a case where the insitu soils are deemed unworkable (e.g. too wet), they should be replaced with suitable drier fill material ex insitu or from commercial sources. The presence of shallow rock or outcrops will affect excavations for foundations, service trenches and platforming, and allowance must be made for heavy excavators and rock bucket attachments. No blasting is required, but in places where the calcrete is hard/thick, hydraulic attachments (pecker) may be required to wedge & split.

The recommended foundation system for single and double storey structures across the entire site is lightly reinforced strips or light rafts on well compacted insitu soils or engineered platforms (min G9, compacted to 93% of MDD). Fill under raft floor slabs should be at least G7 material below the foundation (recommend min 0.3m, compacted to 93% Mod AASHTO). Design bearing pressures should be limited to 75kPa.

8.2 Road pavements

Roads should be constructed in accordance with SABS 1200, COLTO, TRH4, TRH14, TRH15, The Red Book and/or other applicable specifications and standards, or as directed by the engineer.

Test results indicate that the subgrade quality is highly variable but generally consisting of good/fair subgrade conditions (G7, SG class 1). It is recommended that G7 quality is assumed for design purposes, but at the engineer's discretion, allowance can be made for importation of a G7 upper SSG layer to create a uniform subgrade layer for ease of compaction of the subbase. Subbase and base course material would have to be imported as per normal.

General preparation of the subgrade:

- Cut roadbed to line and level;
- Rip 150mm insitu soil and compact to 90% of Mod. AASHTO density (LSSG). Recommended moisture content before rolling is optimum moisture content (OMC) minus 2%;
- Remove any incompressible or wet soil and reinstate with imported G7 material or suitably drier organic-free *in situ* soil, as directed by the engineer.
- Place 150mm G7 (ex insitu or imported from commercial sources) and compact to 93% MDD (USSG).

Table 8 serves as a guideline for the design of a Category C flexible pavement in a moderate climatic region with a design life of 15 years with traffic loading of less than 3×10^6 E80s over 20 years (as per TRH4).

Table 8: Road layerworks recommendations (Cat C in moderate climate)

<i>Layer</i>	<i>Material</i>	<i>Thickness mm</i>	<i>Required Compaction</i>
Seal	Cape Seal	13/19	TBD by engineer
Base	Imported G2/3	150	100% MDD
Subbase	Imported G5	150	95% MDD
USSG	Insitu/imported G7	150	93% MDD
LSSG	Insitu G7	150	93% MDD
OR			
Seal	n/a	n/a	n/a
Base	Interlocking cement pavers	80	n/a
Subbase	C4 (Imported G4/5)	150	95% MDD
USSG	Insitu/imported G7	150	93% MDD
LSSG	Insitu G7	150	93% MDD

9. Storm water drainage recommendations

The design and construction of storm water drainage should be carried out in accordance with SABS 1200LE, COLTO, TRH15, The Red Book or other applicable standards, or as directed by the engineer.

Irregular slope gradients, topographic depressions and the presence of natural drainage lines will affect stormwater drainage, and the design of stormwater systems will require

careful attention. Infiltration into the soil can be slow and restricted by shallow rock, and a significant portion of rainfall will end up as run-off or standing water. The design of storm water systems will have to ensure effective site drainage during flood events. Underground piped storm-water systems with drop inlets are recommended to cater for minor flood events, and major flood waters should be accommodated along roads. To this end, raised barrier kerbs, mountable or semi-mountable kerbs along roads are recommended in order to channel storm water along roads and prevent over-topping into erven. Subsoil drains along roads are not envisaged due to the dearth of clayey subgrade soils or shallow water tables.

The ponding of storm water around the exterior of houses can be avoided by shaping the ground levels around the exterior to create a fall away from the house and constructing a 1m wide a concrete apron with a 10% fall away from the house. This will also assist in maintaining ground moistures stable and minimising erosion around the house. The finished floor level of all houses should be a minimum of 150mm above final ground level to prevent flooding.

10. Special precautionary measures


There are no special geotechnical engineering measures envisaged for this site.

11. Conclusions

The geotechnical investigations indicate that the site geology and ground conditions are generally suitable for the proposed development with conventional engineering, but there are some geotechnical constraints which may impact on the engineering design and subsidy variations and will require consideration by the designers.

Appendix 1

Maps




Legend

 Site Location


Client: Asla Devco
Project: Subsidy Housing
Site: Ptn 111 of
Melkhoutfontein 480
Area: Stilbaai

Drawing Name: Locality Map
Drawing No:
Date: 08 February 2018
Revision: 0
Drawn By: S Ngema
Checked By: I Paton

Scale 1:1250000

0 6 12 18 24 30 km



PO Box 964
Knysna
6570
044-3820502
iain@outeniqua.co.za



Legend

Site Boundry

Client: Asla Devco
Project: Subsidy Housing
Site: Ptn 111 of
Melkhoutfontein 480
Area: Stilbaai

Drawing Name: Topographic
Map
Drawing No:
Date: 08 February 2018
Revision: 0
Drawn By: S Ngema
Checked By: I Paton

Scale 1:12500
0 60 180 300 m



PO Box 964
Knysna
6570
044-3820502
iain@outeniqua.co.za



Legend

- Topo vector
- River
- Site Boundry




Client: Asla Devco
Project: Subsidy Housing
Site: Ptn 111 of
Melkhoutfontein 480
Area: Stilbaai

Drawing Name: Topographic
Map
Drawing No:
Date: 08 February 2018
Revision: 0
Drawn By: S Ngema
Checked By: I Paton

Scale 1:10000
0 50 150 250 m




PO Box 964
Knysna
6570
044-3820502
iain@outeniqua.co.za




Client: Asla Devco
Project: Subsidy Housing
Site: Ptn 111 of
Melkhoutfontein 480
Area: Stilbaai

Drawing Name: Geological
Map
Drawing No:
Date: 27 November 2017
Revision: 0
Drawn By: S Ngema
Checked By: I Paton



PO Box 964
Knysna
6570
044-3820502
ia@outeniqua.co.za



Legend

- Topo vector
- River
 - Site Boundry
 - Terrain 1(C1/R)
 - Test positions

Client: Asla Devco
Project: Subsidy Housing
Site:Ptn 111 of
Melkhoutfontein 480
Area:Stilbaai

Drawing Name:
Geotechnical Map
Drawing No:
Date: 19 February 2018
Revision: 0
Drawn By: S Ngema
Checked By: I Paton

Scale 1:3500
0 15 45 75 m



PO Box 964
Knysna
6570
044-3820502
ia@outeniqua.co.za

Appendix 2

Test pit profiles




OUTENIQUA

GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client:	Asla Devco
Project:	Subsidy Housing Project, Portion 111 of Melkhoutfontein 480
Area:	Still Bay
Date:	29.11.17
Excavator:	TLB






OUTENIQUA

GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client:	Asla Devco
Project:	Housing Project, Portion 111 of Melkhoutfontein 480
Area:	Still Bay
Date:	29.11.17
Excavator:	TLB






OUTENIQUA GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client:	Asla Devco
Project:	Housing Project, Portion 111 of Melkhoutfontein 480
Area:	Still Bay
Date:	29.11.17
Excavator:	TLB






OUTENIQUA

GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client:	Asla Devco
Project:	Housing Project, Portion 111 of Melkhoutfontein 480
Area:	Still Bay
Date:	29.11.17
Excavator:	TLB






OUTENIQUA

GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client:	Asla Devco
Project:	Housing Project, Portion 111 of Melkhoutfontein 480
Area:	Still Bay
Date:	29.11.17
Excavator:	TLB






OUTENIQUA

GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client:	Asla Devco
Project:	Housing Project, Portion 111 of Melkhoutfontein 480
Area:	Still Bay
Date:	29.11.17
Excavator:	TLB






OUTENIQUA

GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client:	Asla Devco
Project:	Housing Project, Portion 111 of Melkhoutfontein 480
Area:	Still Bay
Date:	29.11.17
Excavator:	TLB






OUTENIQUA

GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client:	Asla Devco
Project:	Housing Project, Portion 111 of Melkhoutfontein 480
Area:	Still Bay
Date:	29.11.17
Excavator:	TLB






OUTENIQUA

GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client:	Asla Devco
Project:	Housing Project, Portion 111 of Melkhoutfontein 480
Area:	Still Bay
Date:	29.11.17
Excavator:	TLB





OUTENIQUA

GEOTECHNICAL SERVICES

Geotechnical Soil Profile

Client: Asla Devco
Project: Housing Project, Portion 111 of Melkhoutfontein 480
Area: Still Bay
Date: 29.11.17
Excavator: TLB

TP 19

Datum: NGL

Co-ords:

21 Y-037338 X3800193

Key to symbols:

● Sample taken

▼ Groundwater

Dynamic Cone Penetrometer (DCP)

Photo of Test Pit

A
B




0
500
1000
1500
2000
2500
3000

(0 to 150)
(150 to 300)

Moist, black, medium dense, intact, **SHALE GRAVEL**, imported (fill)
Light brown to light yellow, highly weathered, medium grained, cross
bedded, soft to medium hard rock, **CALCARENITE**.

Refusal on rock
No water table



Appendix 3

Lab test data



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	1/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Dark Yellowish Orange Clayey Sand	Sample Number:	68642		
Position:	TP3 - Layer 3	Liquid Limit	20	Linear Shrinkage	1.5
Depth:	1700-2300	Plasticity Index	3	Insitu M/C%	13.2

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	100
26.5	100
19.0	100
13.2	100
9.5	99
6.7	99
4.75	99
2.36	98
1.18	97
0.600	94
0.425	86
0.075	24
0.0690	23
0.0494	21
0.0223	20
0.0064	20
0.0045	20
0.0032	20
0.0023	19
0.0013	19



% Clay	19	% Silt	5	% Sand	74	% Gravel	2
Unified Soil Classification		SM		PRA Soil Classification		A-2-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	2/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Light Brown Gravelly Sand	Sample Number:	68643		
Position:	TP4 - Layer 2	Liquid Limit	23	Linear Shrinkage	2
Depth:	200-800	Plasticity Index	4	Insitu M/C%	16

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	100
26.5	100
19.0	100
13.2	99
9.5	94
6.7	86
4.75	82
2.36	74
1.18	68
0.600	61
0.425	51
0.075	17
0.0632	17
0.0462	15
0.0209	14
0.0062	12
0.0044	11
0.0032	11
0.0023	9
0.0013	9



% Clay	9	% Silt	9	% Sand	54	% Gravel	28
Unified Soil Classification		SM-SC		PRA Soil Classification		A-2-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	3/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Dark Yellowish Orange Clayey Sand	Sample Number:	68644		
Position:	TP4 - Layer 3	Liquid Limit	NP	Linear Shrinkage	0
Depth:	800-1400	Plasticity Index	NP	Insitu M/C%	12.6

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	100
26.5	100
19.0	100
13.2	100
9.5	100
6.7	100
4.75	100
2.36	100
1.18	99
0.600	97
0.425	88
0.075	16
0.0685	16
0.0490	15
0.0221	14
0.0064	13
0.0045	13
0.0032	13
0.0023	11
0.0013	11



% Clay	11	% Silt	5	% Sand	83	% Gravel	1
Unified Soil Classification		SM		PRA Soil Classification		A-2-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	4/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Light Green Clayey Sand	Sample Number:	68645		
Position:	TP4 - Layer 4	Liquid Limit	18	Linear Shrinkage	2
Depth:	1400-3000	Plasticity Index	2	Insitu M/C%	23.2

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	100
26.5	100
19.0	100
13.2	100
9.5	100
6.7	100
4.75	100
2.36	100
1.18	100
0.600	98
0.425	92
0.075	25
0.0690	24
0.0498	21
0.0223	20
0.0065	20
0.0046	20
0.0032	20
0.0023	19
0.0013	19



% Clay	19	% Silt	6	% Sand	75	% Gravel	0
Unified Soil Classification		SM		PRA Soil Classification		A-2-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	5/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Light Yellowish Orange to Light Green Clayey Sand	Sample Number:	68647		
Position:	TP6 - Layer 3	Liquid Limit	16	Linear Shrinkage	1
Depth:	1500-2500	Plasticity Index	2	Insitu M/C%	18.9

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	100
26.5	100
19.0	100
13.2	100
9.5	100
6.7	100
4.75	100
2.36	100
1.18	100
0.600	99
0.425	92
0.075	17
0.0704	16
0.0505	14
0.0226	14
0.0065	14
0.0046	14
0.0033	14
0.0023	13
0.0013	13



% Clay	13	% Silt	4	% Sand	83	% Gravel	0
Unified Soil Classification		SM		PRA Soil Classification		A-2-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	6/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Dark Reddish Brown Sand	Sample Number:	68648		
Position:	TP7 - Layer 1	Liquid Limit	NP	Linear Shrinkage	0
Depth:	0-400	Plasticity Index	NP	Insitu M/C%	6.9

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	100
26.5	100
19.0	100
13.2	100
9.5	100
6.7	100
4.75	100
2.36	100
1.18	99
0.600	97
0.425	87
0.075	6
0.0741	6
0.0537	4
0.0242	3
0.0070	3
0.0049	3
0.0035	3
0.0025	2
0.0014	2



% Clay	2	% Silt	4	% Sand	94	% Gravel	0
Unified Soil Classification		SP-SM		PRA Soil Classification		A-3 / A-2-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	7/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Dark Reddish Brown Gravelly Sand	Sample Number:	68649		
Position:	TP12 - Layer 1	Liquid Limit	21	Linear Shrinkage	1
Depth:	0-300	Plasticity Index	2	Insitu M/C%	15.6

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	100
26.5	90
19.0	85
13.2	84
9.5	83
6.7	81
4.75	81
2.36	79
1.18	77
0.600	75
0.425	71
0.075	18
0.0676	17
0.0498	13
0.0223	13
0.0066	11
0.0047	10
0.0033	9
0.0024	9
0.0014	9



% Clay	9	% Silt	9	% Sand	60	% Gravel	22
Unified Soil Classification		SM		PRA Soil Classification		A-2-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	8/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Light Yellowish Orange Clayey Silty Sand	Sample Number:	68651		
Position:	TP12 - Layer 3	Liquid Limit	NP	Linear Shrinkage	0
Depth:	700-1600	Plasticity Index	NP	Insitu M/C%	6.5

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	100
26.5	100
19.0	100
13.2	100
9.5	100
6.7	99
4.75	99
2.36	98
1.18	97
0.600	95
0.425	94
0.075	53
0.0715	48
0.0519	37
0.0234	32
0.0068	29
0.0049	27
0.0034	24
0.0024	24
0.0014	24



% Clay	24	% Silt	25	% Sand	48	% Gravel	3
Unified Soil Classification		ML		PRA Soil Classification		A-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqualab.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	9/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Light Yellowish Orange Gravelly Sand	Sample Number:	68652		
Position:	TP14 - Layer 2	Liquid Limit	NP	Linear Shrinkage	0
Depth:	300-2200	Plasticity Index	NP	Insitu M/C%	8.3

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	88
26.5	80
19.0	74
13.2	67
9.5	62
6.7	59
4.75	58
2.36	54
1.18	52
0.600	49
0.425	43
0.075	7
0.0715	7
0.0513	6
0.0232	5
0.0067	5
0.0048	4
0.0034	4
0.0024	4
0.0014	4



% Clay	4	% Silt	3	% Sand	47	% Gravel	46
Unified Soil Classification		SP-SM		PRA Soil Classification		A-1-b / A-2-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd

Materials Testing Laboratory

Registration No. 95/07742/07

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-FIND-1-5

Dec-14


Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay		
	P O Box 118	Date Received :	05/12/17		
	Gordons Bay	Date Reported :	25/01/18		
	7151	Req. Number :	4026/17		
Attention :	David Douglas	No. of Pages :	10/12		

TEST REPORT



FOUNDATION INDICATOR - (TMH 1 Method A1(a),A2,A3,A4,A5) & (ASTM Method D422)

Material Description:	Light Greyish Yellow Silty Gravelly Clayey Sand	Sample Number:	68654		
Position:	TP17 - Layer 2	Liquid Limit	16	Linear Shrinkage	1
Depth:	300-700	Plasticity Index	3	Insitu M/C%	14.4

Sieve Size(mm)	% Passing
75.0	100
63.0	100
53.0	100
37.5	100
26.5	100
19.0	100
13.2	93
9.5	90
6.7	89
4.75	88
2.36	86
1.18	85
0.600	83
0.425	81
0.075	37
0.0690	36
0.0498	31
0.0223	30
0.0065	28
0.0046	27
0.0033	25
0.0023	24
0.0014	24



% Clay	24	% Silt	13	% Sand	48	% Gravel	15
Unified Soil Classification		SM		PRA Soil Classification		A-4	



Notes:

- Specimens sampled by Outeniqua Lab according to sampling Plan TMH 5 Methods MB1 & MC1
- All specimen sampled by : 0
- The weather conditions are such that there is no detrimental effect on the sample taken.

- Sampling falls outside the scope of Outeniqua Lab's SANAS accreditation.
- The test results are reported with an approximate 95% level of confidence.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Technical Director of Outeniqua Lab (Pty) Ltd.
- Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- Measuring Equipment, traceable to National Standards is used where applicable.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

L. Heathcote (Director)
For Outeniqua Lab (Pty) Ltd.



OUTENIQUA LAB (Pty) Ltd.

Registration No. 95/07742/07

Materials Testing Laboratory

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqua.co.za

R-CBR-1-7

Nov-16







T0347

Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay
	PO Box 118	Date Received :	05/12/17
	Gordons Bay	Date Reported :	01/02/18
	7151	Req. Number :	4026/17
Attention :	David Douglas	No. of Pages :	11/12

TEST REPORT

CALIFORNIA BEARING RATIO - (TMH 1 Method A1(a),A2,A3,A4,A5,A7,A8)

Material Indicators										68646	
Sample Position (SV)		TP 5 - Layer 1		TRH 14:		TP 12 - Layer 2		TRH 14:			
Depth (mm)		0-900		G7 SSG		300-700		G6 Subbase			
Sample No		68646				68650					
Materials Description	Source	In-Situ Dark Reddish Brown SILTY Sand Existing			In-Situ Light Brown Silty Sandy Gravel with Cobbles Existing						
	Colour										
	Soil Type										
	Classification										
Max. Stone size in hole (mm)				Opinion				Opinion			
Percentage Passing	75.0mm	100				100					
	63.0mm	100				100					
	53.0mm	100				100					
	37.5mm	100				95					
	26.5mm	100				88					
	19.0mm	100				83					
	13.2mm	100				76					
	4.75mm	100				64					
	2.00mm	100				58					
	0.425mm	84				48					
0.075mm	15.1		16.0								
Soil Mortar & Constants										68650	
Grading Modulus		1.01	0.75 - 2.70	✓	1.78		1.20 - 2.60	✓			
Coarse Sand (%)		16			17						
Fine Sand (%)		69			56						
Silt & Clay (%)		15			28						
Liquid Limit (%)		NP			27						
Plasticity Index (%)		NP	≤ 12	✓	3		≤ 12	✓			
Linear Shrinkage (%)		0.0			2.0						
CBR / Density Relationship											
MOD	Max Dry Density (kg/m³)	1842			1775						
	Opt Moisture Content (%)	9.7			15.3						
	Mould Moisture Con. (%)	9.7			15.2						
	@100% Mod AASHTO	100.1			100.8						
	Swell (%)	0.00	≤ 1.5	✓	0.00		≤ 1.0	✓			
NRB	100% NRB	95.7			95.6						
	Swell (%)	0.00			0.00						
Proc	100% Proctor	92.0			92.2						
	Swell (%)	0.00			0.00						
CBR	@ 100% Mod AASHTO	38			68						
	@ 98% Mod AASHTO	33			56						
	@ 95% Mod AASHTO	25			43						
	@ 93% Mod AASHTO	17	≥ 15	*	28		≥ 25	*			
	@ 90% Mod AASHTO	10			14						
Insitu Moisture Content (%)											
Soil Classification Achieved By The Material										● 68646 ■ 68650	
TRH 14:		G7 SSG				G6 Subbase					
AASHTO System		A-2-4				A-1-b / A-2-4					
Unified System		SM				GM					
Wearing Course Graph (TRH 20)											
Shrinkage Product (Sp)											

Specimens delivered to Outeniqua Lab in good order.

Llewelyn Heathcote
Technical Signatory
For Outeniqua Lab (Pty) Ltd.

Copyright © 2014 Llewelyn Heathcote. All Rights Reserved.

- The opinion column is an interpretation of the direct comparison between the quoted specification and the single test sample results obtained. The compliant (P), non compliant (I) and uncertain (U) opinion indicators are based on an approximate 95% level of confidence with reference to SAMM GUIDANCE 1, Issue 2 : 20 June 2007 Section 2.
- The uncertain (U) indicates that the test result is either equal to or is above / below the specified limit by a margin less than the measurement uncertainty; it is therefore not possible to state compliant (P) or non compliant (I) based on a 95% level of confidence with reference to SAMM GUIDANCE 1, Issue 2 : 20 June 2007 Section 2.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Director of Outeniqua Lab (Pty) Ltd.
- Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab (Pty) Ltd nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Director: L Heathcote B-Tech. (Civil Eng.) & BSc Hons (Transport)



OUTENIQUA LAB (Pty) Ltd.

Registration No. 95/07742/07

Materials Testing Laboratory

6 Mirrorball Street, George : PO Box 3186, George Industria, 6536

Tel: 044 8743274 : Fax: 044 8745779 : e-mail: llewelyn@outeniqualab.co.za

R-CBR-1-7

Nov-16



T0347

Customer :	Asla Devco	Project :	Subsidy Housing Projects on Portion 111 of Melkhoutfontein 480 - Still Bay
	PO Box 118	Date Received :	05/12/17
	Gordons Bay	Date Reported :	30/01/18
	7151	Req. Number :	4026/17
Attention :	David Douglas	No. of Pages :	12/12

TEST REPORT

CALIFORNIA BEARING RATIO - (TMH 1 Method A1(a), A2, A3, A4, A5, A7, A8)

Material Indicators									
Sample Position (SV)		TP 14 - Layer 2		TRH 14:		TP 15 - Layer 2		TRH 14:	
Depth (mm)		300-2200		G7 SSG		250-800		G7 SSG	
Sample No		68652				68653			
Materials Description	Source	In-Situ			In-Situ				
	Colour	Light Yellowish Orange			Light Yellowish Orange - White				
	Soil Type	Gravelly Sand			Sandy Gravel with Gabbles + Boulders				
	Classification	Existing			Existing				
Max. Stone size in hole (mm)									
Percentage Passing	75.0mm	100		Opinion	100		Opinion		
	63.0mm	100			100				
	53.0mm	100			100				
	37.5mm	90			90				
	26.5mm	83			82				
	19.0mm	77			73				
	13.2mm	67			63				
	4.75mm	54			50				
	2.00mm	43			39				
	0.425mm	33			27				
0.075mm	11.0			8.5					
Soil Mortar & Constants									
Grading Modulus		2.13	0.75 - 2.70	✓	2.25	0.75 - 2.70	✓		
Coarse Sand (%)		24			30				
Fine Sand (%)		50			48				
Silt & Clay (%)		26			22				
Liquid Limit (%)		NP			NP				
Plasticity Index (%)		NP	≤ 12	✓	NP	≤ 12	✓		
Linear Shrinkage (%)		0.0			0.0				
CBR / Density Relationship									
MOD	Max Dry Density (kg/m³)	1858			1812				
	Opt Moisture Content (%)	11.6			15.4				
	Mould Moisture Con. (%)	11.6			15.1				
	@100% Mod AASHTO	100.0			100.0				
	Swell (%)	0.00	≤ 1.5	✓	0.00	≤ 1.5	✓		
Proc NRB	100% NRB	95.6			95.8				
	Swell (%)	0.00			0.00				
	100% Proctor	92.8			91.6				
CBR	Swell (%)	0.00			0.00				
	@ 100% Mod AASHTO	52			65				
	@ 98% Mod AASHTO	41			50				
	@ 95% Mod AASHTO	27			31				
	@ 93% Mod AASHTO	20	≥ 15	✓	20	≥ 15	✓		
	@ 90% Mod AASHTO	12			11				
Insitu Moisture Content (%)									
Soil Classification Achieved By The Material									
TRH 14:		G7 SSG				G7 SSG			
AASHTO System		A-1-b / A-2-4				A-1-a / A-1-b / A-2-4			
Unified System		GP-GM				GP-GM			

68652

Sieve Analysis

CBR Chart

68653






Sieve Analysis

CBR Chart

68652

68653

Wearing Course Graph (TRH 20)



Specimens delivered to Outeniqua Lab in good order.

Llewelyn Heathcote
Technical Signatory
For Outeniqua Lab (Pty) Ltd.

Copyright © 2014 Llewelyn Heathcote. All Rights Reserved.

- The opinion column is an interpretation of the direct comparison between the quoted specification and the single test sample results obtained. The compliant (P), non compliant (I) and uncertain (U) opinion indicators are based on an approximate 95% level of confidence with reference to SAMM GUIDANCE 1, Issue 2 : 20 June 2007 Section 2.
- The uncertain (U) indicates that the test result is either equal to or is above / below the specified limit by a margin less than the measurement uncertainty; it is therefore not possible to state compliant (P) or non compliant (I) based on a 95% level of confidence with reference to SAMM GUIDANCE 1, Issue 2 : 20 June 2007 Section 2.
- This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Director of Outeniqua Lab (Pty) Ltd.
- Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
- While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab (Pty) Ltd nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Director: L Heathcote B-Tech. (Civil Eng.) & BSc Hons (Transport)



Controlab South Africa (Pty) Ltd

CIVIL ENGINEERING MATERIAL AND GEOTECHNICAL LABORATORY,
GEOTECHNICAL AND ENVIRONMENTAL SERVICES

www.controlab.co.za

HEAD OFFICE: 1 Alfred Road, Vincent 5247, Tel: 043 726 7859, Fax: 043 726 7426

CENTRAL LABORATORY : 10 St Pauls Road, East London, 5201, Tel: 043 722 5420 / 722 8565, Fax: 043 743 9942, P O Box 346, East London, 5200

OTHER BRANCH OFFICES: Cape Town, Kokstad, Johannesburg, Mthatha, Queenstown, Lusaka - Zambia

CONSOLIDATION TEST

SUMMARY OF READINGS

CLIENT: Outeniqua Geotechnical Services
PROJECT : MELKHOUTFONTEIN, STILBAAI, WC

PROJECT NO : 88293

SAMPLE NO : 8179

POSITION: TP4

DEPTH: 2000mm

INITIAL DIAL READING = 5.268 mm

RING DIAMETER = 71 mm

H₁ = 19.7 mm

H_s = 12.0579 mm

Dial Gauge Div = 1

OEDOMETER NO : 5

BEAM RATIO : 11

BEAM LOAD	COMMENTS	PRESSURE	DIAL READING	UNCORRECTED DEFLECTION	MACHINE CORRECTION	CORRECTED DEFLECTION	HEIGHT CHANGE	VOID RATIO
(kg)		(Kpa)	(mm)	(mm)	(mm)	(mm)	(mm)	
0.1		2.73	5.268	0.000	0.000	0	19.700	0.6338
1.1		29.98	5.872	-0.604	0.000	0.604	19.096	0.5837
2.1		57.24	6.048	-0.780	0.000	0.780	18.920	0.5691
2.1	sat	57.24	6.056	-0.788	0.000	0.788	18.912	0.5684
4.1		111.75	6.312	-1.044	0.000	1.044	18.656	0.5472
8.1		220.77	8.330	-3.062	0.000	3.062	16.638	0.3798
16.1		438.81	9.148	-3.880	0.000	3.880	15.820	0.3120
32.1		874.90	9.688	-4.420	0.000	4.420	15.280	0.2672
16.1		438.81	9.620	-4.352	0.000	4.352	15.348	0.2729
8.1		220.77	9.564	-4.296	0.000	4.296	15.404	0.2775
4.1		111.75	9.522	-4.254	0.000	4.254	15.446	0.2810
2.1		57.24	9.476	-4.208	0.000	4.208	15.492	0.2848
1.1		29.98	9.430	-4.162	0.000	4.162	15.538	0.2886
0.1		2.73	9.056	-3.788	0.000	3.788	15.912	0.3196
1.1		29.98	9.146	-3.878	0.000	3.878	15.822	0.3122
2.1		57.24	9.218	-3.950	0.000	3.950	15.750	0.3062
4.1		111.75	9.350	-4.082	0.000	4.082	15.618	0.2952
8.1		220.77	9.466	-4.198	0.000	4.198	15.502	0.2856
16.1		438.81	9.574	-4.306	0.000	4.306	15.394	0.2767
32.1		874.90	9.756	-4.488	0.000	4.488	15.212	0.2616
16.1		438.81	9.718	-4.450	0.000	4.450	15.250	0.2647
8.1		220.77	9.688	-4.420	0.000	4.420	15.280	0.2672
4.1		111.75	9.652	-4.384	0.000	4.384	15.316	0.2702
2.1		57.24	9.620	-4.352	0.000	4.352	15.348	0.2729
1.1		29.98	9.578	-4.310	0.000	4.310	15.390	0.2763
0.1		2.73	9.128	-3.860	0.000	3.860	15.840	0.3137

COLLAPSE 0.0

The above test results are pertinent to the samples received and tested only.

While the tests are carried out according to recognized standards Controlab shall not be liable for erroneous testing or reporting thereof.

This report may not be reproduced except in full without prior consent of Controlab.

Technical Signatory:

C Becker



Controlab South Africa (Pty) Ltd

CIVIL ENGINEERING MATERIAL AND GEOTECHNICAL LABORATORY,
GEOTECHNICAL AND ENVIRONMENTAL SERVICES

www.controlab.co.za

HEAD OFFICE: 1 Alfred Road, Vincent 5247, Tel: 043 726 7859, Fax: 043 726 7426

CENTRAL LABORATORY : 10 St Pauls Road, East London, 5201, Tel: 043 722 5420 / 722 8565, Fax: 043 743 9942, P O Box 346, East London, 5200


OTHER BRANCH OFFICES: Cape Town, Kokstad, Johannesburg, Mithata, Queenstown, Lusaka - Zambia

CONSOLIDATION TEST

CLIENT: Outeniqua Geotechnical Services
PROJECT : MELKHOUTFONTEIN, STILBAAI, WC

PROJECT NO : 88293
SAMPLE NO : 8179
POSITION : TP4
DEPTH : 2000mm

CLIENT SAMPLE DESCRIPTION	:	dk Y cly s		
STATE OF SAMPLE	:	Undisturbed	SPECIFIC GRAVITY est.	= 2.69
BULK DENSITY	=	2040	VOL VOIDS	= 0.38792227
DRY DENSITY	=	1646 Kg/m ³	VOL SOILDS	= 0.61207773
INITIAL SATURATION	=	1.01	FINAL SATURATION	= 1.03
INITIAL MOISTURE CONTENT	=	23.90 %	FINAL MOISTURE CONTENT	= 24.2
INITIAL VOID RATIO	=	0.6338	FINAL VOID RATIO	= 0.2848
		COLLAPSE	0.0	



The above test results are pertinent to the samples received and tested only.

While the tests are carried out according to recognized standards Controlab shall not be liable for erroneous testing or reporting thereof.

This report may not be reproduced except in full without prior consent of Controlab.

Technical Signatory:

C Becker



Controlab South Africa (Pty) Ltd

CIVIL ENGINEERING MATERIAL AND GEOTECHNICAL LABORATORY,
GEOTECHNICAL AND ENVIRONMENTAL SERVICES

www.controlab.co.za

HEAD OFFICE: 1 Alfred Road, Vincent 5247, Tel: 043 726 7859, Fax: 043 726 7426


CENTRAL LABORATORY : 10 St Pauls Road, East London, 5201, Tel: 043 722 5420 / 722 8565, Fax: 043 743 9942, P O Box 346, East London, 5200

OTHER BRANCH OFFICES: Cape Town, Kokstad, Johannesburg, Mithatha, Queenstown, Lusaka - Zambia

CLIENT:	Outeniqua Geotechnical Services	PROJECT:	Melkhoutfontein Stilbaai
	P O Box 964		Western Cape
	KNYSNA		
	6570	DATE:	2017-12-15
ATT:	Mr I Paton	REF:	88293

pH & CONDUCTIVITY

SAMPLE NO.	SAMPLE NO. & TEST POSITION	DEPTH mm	pH	Conductivity (mS/m)
8180	TP4PH TP 4	800-1400	7.57	1843
8181	TP7PH TP 7	0-400	6.66	1441
8182	TP17PH TP 17	300-700	8.20	N/A

Technical Signatory: 

C Becker

Appendix 4

DCP test data



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqualab.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	1 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	2 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	3 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	4 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	5 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	7 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	8 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	9 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	10 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqualab.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	11 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	12 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	13 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqualab.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	14 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqualab.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	15 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqualab.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	16 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	17 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	18 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE



Outeniqua Geotechnical Services cc.

R-DCP-1-5

Dec-14

Geotechnical Engineering Consultants

Registration No. 1999/062743/23


18 Clyde Street, Knysna : PO Box 964, Knysna, 6570

Tel: 044 3820502 : Fax: 044 3820503 : e-mail: iain@outeniqua.co.za

Customer :	Asla Devco P.O. Box 118 Gordons Bay 7151	Project :	Subsidy Housing Project on Portion 111 of Melkhoutfontein 480, Still Bay
		Date Received :	20.11.17
		Date Reported :	29.11.17
		Req. Number :	
Attention :	David Douglas	No. of Pages :	19 of 19

TEST REPORT

Dynamic Cone Penetrometer (DCP) - (TMH 6 Method ST6)



I Paton (Member)
For Outeniqua Geotech. Services cc.
Technical Signatory

1. This report (with attachments) is the correct record of all measurements made, and may not be reproduced other than with full written approval from the Members of Outeniqua Geotechnical Services cc.
2. Measuring Equipment, traceable to National Standards is used where applicable. Results reported in this Test Report relate only to the items tested and are an indication only of the sample provided and/or taken.
3. While every care is taken to ensure the correctness of all tests and reports, neither Outeniqua Lab nor its employees shall be liable in any way whatever for any error made in the execution or reporting of tests or any erroneous conclusions drawn therefrom or for any consequence thereof.

Members: Iain Paton BSc Hons MEng Pr Sci Nat MSAIEG MSAICE